EXTRA ITEM RATE LIST

Name of Work: Package 1 Including 5 Works of Rs. 300.00 Lakhs 1) Construction of RCC Drain and Covering Slab at BEL 2nd Block 1st, 2nd, 4th, 5th Cross in Ward No. 10, (Doddabommasandra). 2) Construction of Roads and Drains at BEL 2nd Block 1st, 2nd, 3rd and 4th Main Road in Ward No. 10, (Doddabommasandra). 3) Improvements to Roads and Drains at Chamundeshwari Layout Cross Road in Ward No. 10, (Doddabommasandra). 4) Improvements to Roads and Drains at Nanjappa Layout Cross Road in Ward No. 10, (Doddabommasandra). 5) Improvements to Roads and Drains at Nanjappa Layout Main Road in Ward No. 10, (Doddabommasandra).

Name of Agency: Sri Chidananda Murthy. R, No. 16, 2nd Cross, Vinayaka Layout, Horamavu, Bangalore - 560043.

Estimated Cost: Rs. 3,00,00,000.00

Approved Amount : Rs. 2,78,71,820.76

Work Order No. BBMP/EE/BTP/WO/155/2020-21 Dated: 08.12.2020.

Sl. No.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
1	E1	Providing **precast slab of 100mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - (Data rate Approved).	Sqm	1134.00	2453.62	2782405.08	Additional Item	No	By over all savings in the work	Approved Data Rates	
	E2	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork,	No	2800.00	454.06	1271368.00	Additional Item	No	By over all savings in the work	2018-19 PWD SR Rates	
	E3	KSRB 15-19.1 : Providing and applying ready mix priming coat **over concrete** / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand	Sqm	504.00	41.18	20754.72	Additional Item	No	By over all savings in the work	2018-19 PWD SR Rates	
	E4	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface	Sqm	504.00	94.60	47678.40	Additional Item	No	By over all savings in the work	2018-19 PWD SR Rates	

Sl. No.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
	E5	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less	Rmtr	144.00	217.33	31295.52	Additional Item	No	By over all savings in the work	2019-20 RWS SR Rates	
		Total				**4153501.72**					

Percentage Excess $\frac{\textbf{4153501.72}}{\textbf{27872112.79}} \times 100 =$ 14.90%

Approved Tender Amount

Assistant Engineer
Ward No. 10

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore - 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ